

Standard 2nd Floor Restrooms & Corridors
December 17, 2021

Notes

- Yellow shaded area to be finished similar to Metropolitan
- Remaining shaded areas to be left unfinished
- Corridor and demising walls between tenant spaces to run to deck above. Restroom walls to terminate above ceiling.
- Corridor walls 1 hr rated. Demising walls unrated, insulated for sound. Drywall both sides. Paint on finished side only. Level 4 finish where painted. Taped on unfinished side.
- Existing electric heaters, lights, etc. in unfinished spaces to remain except as needed to accommodate new construction
- ACT ceilings in corridors to be 10'-0" a.f.f.
- GWB ceilings in restrooms to be 8'-0" a.f.f.

SEE A-141 FOR NOTES & LEGEND
SEE A-070 FOR FINISH SCHEDULE
SEE A-600 SERIES FOR UNIT FINISH PLAN INFORMATION

THE STANDARD
AT STATE
COLLEGE
330 W. COLLEGE AVE.
STATE COLLEGE, PA
16801

LCD
ACQUISITIONS,
LLC
315 O'CONNOR STREET,
ATHENS, GA 30601

Construction
Documents

drawing information:

drawing by:	JMP, SP, NB, LK	
drawing checked by:	AB	
drawing scale:	1/8" = 1'-0"	
drawing date:		
project number:	16113.00	
drawing revisions:		
No.	Description	Date
1	Bulletin 001	10/10/2018
2	Bulletin 009 - CRCA Comments Response	12/21/2018
3	Bulletin 029	04/10/2020
4	Bulletin 041	09/14/2020
5	Bulletin 049	03/08/2021

P2 -
Second
Floor Finish
Plan

A-142

Partition Types

Unrated. Includes sound insulation.

1hr Rated

